

### INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

(51) International Patent Classification 4: G01N 21/00, 31/00, 33/00 G01N 35/02, B01L 3/00 C12M 1/34, 1/36

(11) International Publication Number:

WO 86/ 02163

A1

(43) International Publication Date:

10 April 1986 (10.04.86)

(21) International Application Number: PCT/US85/01851

(22) International Filing Date: 25 September 1985 (25.09.85)

(31) Priority Application Number:

656,755

(32) Priority Date:

1 October 1984 (01.10.84)

(33) Priority Country:

(71) Applicant: AMERICAN HOSPITAL SUPPLY COR-PORATION [US/US]; One American Plaza, Evanston, IL 60201 (US).

(72) Inventors: ELBERT, Lawrence, Emil; 1116 Acacia Avenue, Huntington Beach, CA 92648 (US). STARK, William, A.; 3088 Samoa, Costa Mesa, CA 92626 (US).

(74) Agent: GREEN, Clarence, A.; Perman & Green, 425 Post Road, Fairfield, CT 06430 (US).


Published With international search report.

patent), JP, NL (European patent).

(81) Designated States: CH (European patent), DE (European patent), FR (European patent), GB (European

(54) Title: TABLET DISPENSING

(57) Abstract



A unique method and apparatus for dispensing tablets (T) having particular application in the clinical analysis of biological samples. A series of containers (24) are advanced past a plurality of processing stations, one of which is a tablet dispenser (40) in turn. The processing stations are selectively activated by a controller (100). A sensor (200) is associated with the tablet dispenser (40) and is arranged to detect whether a tablet (T) has actually entered a container (24). The sensor (200) is activated only when the tablet dispenser (40) is activated. The controller (100) is responsive to the sensor (200) in dependence upon the condition sensed by the sensor (200).

# FOR THE PURPOSES OF INFORMATION ONLY

Codes used to identify States party to the PCT on the front pages of pamphlets publishing international applications under the PCT.

AT	Austria	GA	Gabon	MR	Mauritania
AU	Australia	GB	United Kingdom	MW	Malawi
BB	Barbados	HU	Hungary	NL	Netherlands
BE	Belgium	IT	Italy	NO	Norway
BG	Bulgaria	JР	Japan	RO	Romania
BR	Brazil	KP	Democratic People's Republic	SD	Sudan
CF	Central African Republic		of Korea	SE	Sweden
CG	Congo	KR	Republic of Korea	SN	Senegal
CH	Switzerland	LI	Liechtenstein	SU	Soviet Union
CM	Cameroon	LK	Sri Lanka	TD	Chad
DE	Germany, Federal Republic of	LU	Luxembourg	TG	Togo
DK	Denmark	MC	Monaço	US	United States of America
FI	Finland	MG	Madagascar		
FR	France	ML	Mali		

20

25

#### TABLET DISPENSING

#### BACKGROUND OF THE INVENTION

This invention relates generally to the dispensing of tablets, especially for use in the clinical analysis of biological samples. In particular, the invention relates to apparatus for dispensing tablets and to clinical analysis systems for the analysis of biological samples incorporating such apparatus. It also relates to methods of tablet dispensing and methods of clinical analysis employing tablet dispensing.

The present invention is particularly useful in automated clinical analyzers for determining the presence and levels of one or more selected constituents in relatively small biological liquid samples. Numerous automated clinical analyzers are known and widely used in hospital clinical laboratories. A preferred form of such analyzers is known as a single track clinical analyzer in which a series of cuvettes is advanced in turn past a plurality of processing stations arranged in line and the processing stations are selectively activated in varying permutations for different cuvettes.

An automated single track clinical analyzer

10

15

20

25

30

is described in commonly owned U.S. Patent Application Serial No. 284,840, filed July 20, 1981 entitled, "Automated Analysis Instrument System." The single track analyzer can perform different analytical profiles (i.e., profile analysis) or the same analytical test on a series of different patient samples (i.e., batch analysis). In either mode of the single track analyzer, the cuvettes containing samples are processed serially along a single track within the analyzer.

The single track analyzer is capable of performing multiple selected tests on a single specimen and is adapted for handling "stat" testing of emergency samples and routine chemistries. To this end the analyzer is adapted to dispense different permutations of reagent and liquid biological samples into successive, relatively small cuvettes advanced The analyzer has multiple analysis therethrough. stations to which the cuvettes are fed in turn so that examination of the treated samples can be effected at varying time intervals without limiting the throughput of the instrument. These multiple analysis stations permit their positioning at read times that are closely related to theoretical optimal kinetic and endpoint reaction read times.

The single track analyzer utilizes a disposable cuvette belt formed from thin plastic film and defining a series of discrete reaction compartments (cuvettes) which are transported in line through the instrument. The cuvettes are relatively small. They are generally, for example, capable of holding a final reaction volume of approximately 300 microliters. The

20

25

30

patient sample in the cuvette is approximately 2 to 20 microliters. Such a cuvette belt is described in commonly owned U.S. Patent Application Serial No. 284,842, filed July 20, 1981, entitled "Cuvette System For Automated Chemical Analyzers." Such a belt provides handling flexibility and avoids the crosscontamination associated with flow-through cuvettes as well as avoiding the washing required of reusable cuvettes.

10 The earlier clinical analyzers discussed above employed liquid reagent, and mixing of the reagent with the diluent prior to addition of the biological sample was achieved by pipetting a stream of the liquid reagent into the cuvette so as to produce a vortex-type mixing process. A preferred feature of the 15 analyzer disclosed in U.S. Patent Application Serial No. 284,840 is that it is adapted to utilize dry particulate reagents, preferably in tablet form, which are dispensed into the cuvettes from a rotating carousel which can hold a large number of doses. A preferred embodiment of tablet dispenser is described in commonly owned U.S. Patent 4,405,060 entitled "Tablet Dispensing Device".

In order to effect dissolution of the dry particulate reagent within the diluent prior to addition of the biological sample, the reagent and diluent are mixed by ultrasonic means. As disclosed in commonly owned U.S. Patent Application Serial No. 575,924, filed February 1, 1984, entitled "Clinical Analysis Systems and Methods", improved reliability and controllability of the analysis of the samples is achieved by again mixing the contents of the cuvette

10

15

20

25

30

after addition of the sample by directing an air jet to an acute angle against the surface of the liquid in the cuvette. Particularly good mixing is obtained where the air jet is directed at the liquid surface adjacent its junction with the wall of the cuvette, the optimum point of contact of the air jet with the liquid surface being at the meniscus formed at the junction between the liquid surface and the wall of the cuvette.

A further advantageous feature of such an automated clinical analyzer is the use of microprocessor control, particularly for the dispensing and analysis station and the loading and transfer assembly for presenting to the analyzer containers having the samples to be tested.

A particular embodiment of the automated single track clinical analyzer according to aforesaid U.S. Patent application Serial No. 284,840 is the subject of the Paramax Analytical System manufactured by American Dade, a division of American Hospital Supply Corporation, of Miami, Florida. "Paramax" is a registered trademark of American Hospital Supply Corporation. In this system, which is under microprocessor control, a cuvette belt is cut into sections, comprising one or several cuvettes, which are fed in turn past a reagent tablet dispenser, a diluent dispenser, an ultrasonic horn for mixing the reagent and diluent, a sample dispenser and eight photo-optical analyzer stations. During their passage through dispensing and analysis, the cuvettes are supported in a water bath kept at a constant temperature. analysis, the cuvettes pass through a sealing station and into a disposal station.

10

30

Reagent tablets are dispensed from a rotary carousel and the biological liquids to be sampled are delivered in tubes to the sample dispenser one at a time by a carousel having priority access positions to allow immediate "stat" sample entry. Codes on the tubes identify the samples and a code-reader alerts the microprocessor to operate the analyzer in accordance with the coded information. A further reagent dispenser is arranged between two of the analyzer stations for producing further sample reaction to permit additional analysis.

#### SUMMARY OF THE INVENTION

15 The present invention provides an improved clinical analysis system for analyzing biological samples of the kind, as set forth above, including a plurality of processing stations, means for advancing cuvettes past the processing stations in turn and 20 control means for selectively activating the processing stations with respect to the cuvettes whereby different cuvettes are differently processed. Where such a system includes a tablet dispensing means, it may occur sometimes that a tablet is not correctly dispensed, for example because the dispensing means fails or the 25 tablet misses the intended cuvette, with the result that an incorrect analysis will be obtained.

In order to alleviate this problem, the analysis system according to the present invention includes sensing means arranged to sense whether a tablet has entered a cuvette aligned with the dispensing means. The sensing means is activated only

10

15

20

25

30

when the tablet dispensing means is activated and the system control means is responsive to the sensing means in dependence upon the condition sensed by the sensing means.

Such an arrangement has several advantages. The sensing means is arranged to sense whether a tablet has actually entered a cuvette rather than merely sensing that a tablet has been dispensed where the tablet could still fail to enter the cuvette. The sensing means is only activated when the tablet dispensing means is activated which obviates the risk of indicating a failure in cases when no tablet should be dispensed. Further, by making the control means responsive to the condition sensed by the sensing means, effective action can be taken to avoid a faulty analysis being produced by the system.

The control means may be programmed to respond to the sensing means in various ways. Thus, it may merely inhibit further processing of the respective cuvette. However, it is preferred that the system rectify the fault either by reactivating the dispensing means or by processing another cuvette in place thereof. Where the sensing means indicates repeated failure of the tablet dispensing means, for example where it detects two successive failures, the controller may shut down the system for correction of the fault. The error may be reported to the operator and the particular cuvette having the error is flagged in the results printout or the particular test.

During processing, the cuvettes may be partially immersed in liquid to maintain a constant processing temperature. Further, a liquid may be

25

30

dispensed into selected cuvettes before they reach the tablet dispensing means. Thus, a cuvette aligned with the tablet dispensing means may have liquid in it or surrounding it up to a predetermined level. In accordance with a preferred feature of the invention, the sensor is arranged at a level below the mouth of a cuvette aligned with the dispensing means but above the liquid level.

One embodiment of tablet dispenser according to the invention includes a motor for driving the dispenser to dispense a tablet and the sensor is only active when the motor is switched on and in operation, or for a timed interval after the motor is switched on. The sensor may have two light sources and a single detector.

An audio and/or visual warning signal may be generated to indicate to an operator the mis-dispensing of a tablet and/or the shut-down of the machine.

A method of analyzing biological samples is also provided in accordance with the invention in which cuvettes are advanced past a plurality of processing stations in turn and the processing stations are selectively activated with respect to the cuvettes so that different cuvettes are differently processed. One of the processing stations is a tablet dispensing means and the improvement comprises sensing whether a tablet has entered a respective cuvette aligned with the tablet dispensing means only each time the latter is activated and controlling subsequent activation of the processing stations in dependence whether the entry of a tablet into a cuvette has been sensed.

While particularly adapted for use in the

10

15

20

30

clinical analysis of biological samples, the present invention has wider application to the selective dispensing of tablets in general. Thus, from another aspect, the invention provides improved apparatus for dispensing tablets into selected containers advanced therepast which comprises a tablet dispenser and control means for activating the tablet dispenser to dispense a tablet. Sensing means is arranged to sense whether a tablet has entered a container. The sensing means is activated only when the tablet dispenser is activated and the control means is responsive to the sensing means in dependence upon the condition sensed by the sensing means.

In accordance with another feature of the invention, tablets are dispensed into selected containers advanced past a tablet dispenser by a method including the steps of (a) advancing containers in turn past the tablet dispenser, (b) selectively activating the tablet dispenser, (c) sensing whether a tablet has entered a container only each time the tablet dispenser is activated, and (d) controlling subsequent step (a) and/or step (b) in dependence whether the entry of a tablet into a container has been sensed.

#### 25 <u>DESCRIPTION OF THE DRAWINGS</u>

Other features and advantages of the present invention will become apparent from the following description taken in conjunction with the accompanying drawings wherein:

Figure 1 is a schematic plan view of an automated clinical anlyzer according to the present

20

25

30

invention;

Figure 2 is a partial perspective view of the automated clinical analyzer shown in Figure 1;

Figure 3 is a perspective view of a cuvette belt showing one of the cuvettes aligned with the tablet dispenser;

Figure 4 is a plan view of the cuvette belt as shown in Figure 3;

Figure 5 is a block diagram illustrating schematically the control system of the analyzer, and

Figure 6 is another block diagram including a partial schematic illustrating the dispensing and control system in greater detail.

# 15 DETAILED DESCRIPTION

Figures 1 and 2 illustrate an automated clinical analyzer 10 generally as described in the aforesaid U.S. Patent Application Serial No. 575,924. More particularly, the analyzer is a modified Paramax Analytical System as manufactured by American Hospital Supply Corporation. The analyzer 10 is adapted for the testing of constitutents in biological fluids, such as blood samples, urine, etc.

The analyzer comprises a series of processing stations past which strips of disposable reaction cuvettes are indexed or advanced. The cuvettes 24 are supplied from a supply reel 20 as a continuous cuvette belt 22 and are indexed through the analyzer by tractor conveyor 30 which engages a row of index holes in the cuvette belt. The cuvettes are indexed in turn past the following stations: a belt cutter 28 for dividing

10

15

20

25

30

the belt into sections; a tabletted reagent dispenser 40; a diluent and liquid reagent dispenser 50; an ultrasonic mixing horn 14; a sample dispenser 80 for dispensing biological samples delivered by a transfer carousel 64; an air-jet mixing apparatus 15 for mixing the sample with the reagent and diluent in the cuvettes; eight photometric read stations 90; a further reagent dispenser 54; a further air-jet mixing apparatus 15a for mixing the sample and the further reagent; a cuvette sealer 16 and a cuvette collection station 18. During their passage through the analyzer, the cuvettes are carried in a water bath 12 maintained at a constant temperature. An executive or main microprocessor 300 controls the overall operation of the analyzer (as schematically illustrated in Figure 5). The processing stations and their functions will now be described in detail.

The disposable cuvettes 24 are conveniently packaged in reels of as many as 2100 cuvettes. The belt 22 defines entirely separate reaction vessels designed to eliminate cross-contamination of reaction mixtures. The cuvette belt 22 is preferably constructed and made in the manner more fully described in aforesaid U.S. Patent Application Serial No. 284,842, as will now be described briefly with particular reference to Figures 4 and 5.

The belt 22 comprises two strips 111, 112 of transparent plastics material which are molded and sealed together to form a series of discrete, side-by-side parallel compartments (cuvettes) 24 separated by webs 115. The compartments are closed at one end and have an open mouth 117: at the other end so as to

10

15

20

25

30

receive and retain fluid therein. For example, the cuvettes can be in the order of size so as to be capable of holding about 500 microliters of fluid.

The compartments or vessels 24 are substantially rectangular in cross-section, being elongated along the length of the belt. They have generally parallel side faces 124 which define optical windows providing an optical path of precise length through each cuvette for accurate examination of the samples at the read stations 90. The flat web material 115 between the vessels 24 includes a transport strip portion extending alongside the closed ends thereof which is formed with indexing perforations or hole 26. These perforations are engaged by the tractor transport 30 of the analyzer 10 for conveying the cuvettes therethrough and maintaining a precise alignment of the optical paths through the cuvettes with the photooptical examining system at the analysis stations 90.

The transport 30 comprises a single continuous guide and support track extending through the analyzer having a main tractor belt 32 which engages the indexing holes 26 in the cuvette belt 22 and advances the cuvettes through the instrument at a predetermined rate of advance under control of the executive microprocessor 300. A short loading belt 34 threads the cuvette belt 22 into engagement with the main tractor belt 32. The transport 30 advances or indexes the cuvettes through the analyzer 10 in steps corresponding to the spacing between cuvettes (the pitch of the belt) with the cuvettes being stopped and held stationary for a dwell period between each advance. Each step may suitably correspond to a time

10

15

20

25

30

interval of 5 seconds with a 4 second dwell time between each indexing advance of the cuvettes.

The reagent tablet dispenser carousel 42 comprises a circular array of tabletted reagent dispensers 40 and can be rotated to bring the correct solid reagent dispenser to solid reagent dispensing point "SRD" to drop a single reagent tablet 44 into a cuvette 24. As illustrated, the carousel 42 accommodates thirty-two reagent tablet dispensers 40. It is rotated under control of slave microprocessor 302 to bring the correct tablet dispenser to the dispensing point for each cuvette. The dispensers 40 are detachable and can be loaded randomly. An automatic flagging system indicates when a dispenser is low in tablets.

As schematically illustrated in Figures 3 - 6 4, the tablet dispensers 40 are driven by a motor M for dispensing the tablets and, in accordance with the present invention, a sensor 200 disposed beneath the dispensing point "SRD" is arranged to sense whether a tablet actually enters the cuvette 24 aligned with the dispenser 40. The sensor 200 is connected through a feedback circuit (see Figures 5 and 6) to the executive microprocessor 300. This arrangement is described fully hereinbelow.

The diluent and/or liquid reagent dispenser 50 is located adjacent to carousel 42 for adding under the control of slave microprocessor 302 sufficient diluent 52 for reagent tablet 44 dissolution and/or for dispensing a liquid reagent into the reaction vessel (cuvette) 24 at point "LDD". The ultrasonic horn 14 acts on the cuvette contents for a sufficient length of

10

15

20

25

30

time; for example, 45 seconds, to totally dissolve the reagent tablets.

A sample loading and transfer carousel assembly 60 is located downstream of the reagent and diluent dispensers. This carousel assembly, under the control of slave microprocessor 324, comprises a loading carousel 62 into which patient samples 70 are randomly loaded; a transfer carousel 64 which accepts the patient samples 70 from loading carousel 62, identifies the patien t sample by means of a bar code reader 66 which reads a bar code label 72 placed on the patient sample container and coninuously feeds the patient samples into the system; and finally, an unloading carousel 68 receives the patient samples 70 after testing and stores them in an organized manner in the event that they must later be located and retrieved.

The loading carousel 62 permits continuous random loading of up to 96 patient samples. The transfer carousel 64 continuously feeds patient samples into the system for maximum throughput. Standard collection tubes or micro sample tubes may be accommodated thus allowing utilization of the same containers in which the sample was collected; for example, in the case of blood samples, the "Vacutainer" tube which is commonly used to draw the serum specimen.

Sampler 80 for dispensing samples into the cuvettes 24 at point "SD" is located adjacent to transfer carousel 64. This sampler is designed to aspirate about 2 to 20 microliters of patient sample 70 from its container in the transfer carousel and dispense it into a cuvette 24 along with sufficient

10

15

20

25

diluent to make up approximately 100 microliters during the four second dwell period while the cuvette is aligned with the sampler.

The air-jet mixing apparatus 15 (and 15a) direct an air jet at an acute angle against the liquid surface in the cuvette adjacent its junction with the cuvette wall to create a vortex thus producing a thorough mixing of the sample with the reagent and diluent. In a preferred embodiment, the apparatus has a fixed, inclined nozzle and the cuvettes 24 are aligned in position beneath the nozzle and the air jet is switched on only during the dwell period when the cuvette is stationary. In order to ensure that the air jet correctly strikes the liquid surface, the liquid level is closely controlled. The structure and operation of preferred embodiments of the air-jet mixing apparatus 15 and 15a are described in detail hereinafter.

Eight photometric analysis stations 90, which are controlled by slave microprocessor 310, are located at points "SAL" through "SA8" along the cuvette track 30. These analysis stations are connected by individual optical guides 92 and 94 to photo-optical system 100. The station "SAL" is arranged following the ultrasonic horn 14 for verifying proper reagent dispensing and dissolution. This photo-optical system 90 is described and illustrated in commonly owned U.S. Patent Application Serial No. 284,841, filed July 20, 1981, entitled "Multichannel Spectrophotometer".

The second reagent dispenser 54 permits further reaction of the sample to be obtained following initial testing and is shown arranged between analysis

. 30

stations "SA4" and "SA5". It could be located between any of the analysis stations "SA2" to "SA8". This capacity for optional reagent additions or triggered reaction capability gives added analytical versatility for multiple reagent test situations.

The further air-jet mixing apparatus 15a according to the invention provides for thorough remixing of the cuvette contents following addition of further reagent at station 54.

The cuvette sealer 16 seals the tops of the tested cuvettes for convenient clean disposal of completed samples at the cuvette disposal location where they are neatly collected into a lined disposal bin.

The executive microprocessor control system 300 of the clinical analyzer, which suitably has a Z80 processing unit, controls in an overall manner all the operating units thereof in accordance with sample and test information inputted at a suitable operator interface keyboard. In accordance with the desired test results, quantities of a single sample may be dispensed into one or more cuvettes either alone or in combination with any one or more of the solid and liquid reagents and diluent and examined at any one or more of the analysis stations 90. Test results are displayed on a screen and can be printed out.

Normal operation of the instrument system will now be described in detail. A phlebotomist draws a patient blood sample 70 which is positively identified by a bar code label 72 placed on the container in which the sample is drawn. After centrifuging the sample to separate the serum, the

10

15

20

25

30

sample along with as many others as desired is placed in loading carousel 62 which is then placed into the instrument loading and transfer carousel assembly 60. For emergency stat testing, the patient sample 70 may be loaded directly into one of the empty sample receiving slots 65 of transfer carousel 64, or may be exchanged with a sample container already loaded in transfer carousel 65 prior to bar code reader 66.

The loading carousel is then automatically indexed to a position where the patient sample 70 is transferred into an empty sample receiving slot 65 of transfer carousel 64. The transfer carousel 64 then is indexed around to bar code reader 66 which identifies the patient sample. This sample identity is fed to the external data management console 340, which is in operative relationship with executive controller 300, for a scheduled test(s) to be run for this sample that has already been entered into the console 340 by the laboratory technician.

The executive microprocessor 300 then begins the advance of the cuvette supply reel 20 and belt 22 into cuvette track 30 in response to this sample This cuvette supply advance is identification. accomplished by the loading belt 34 which threads the cuvette belt into main transport belt 32. If bar code reader 66 detects that there are no further samples to be tested, the executive microprocessor 300 will activate cuvette belt cutter 28 which divides cuvette belt 22 into sections 29 having a number of cuvettes corresponding to the number of analysis reactions to be performed at a given time. This procedure minimizes waste for single tests or stat situations. Ιn

15

20

25

30

addition, the cuvette belt cutter 28 may also be periodically operated during continuous operation of the instrument in order to prevent the length of the cuvette belt (which must be disposed of) from becoming unmanageable.

As it is fed into the instrument, the cuvette belt 22 enters a water bath 12 which will maintain the reagent and sample reaction mixture at a predetermined incubation temperature. This reaction temperature is generally either 30 degrees C or 37 degrees C.

For the sake of simplicity, it should also be noted that in Figure 1 each circular cuvette position point 25 along cuvette track 30 represents a 5 second period. In other words, every 5 seconds the control microprocessor will step a particular cuvette reaction compartment 24 to the next circular position along the cuvette track 30.

During the time that the transfer carousel 64 is indexing the sample 70 between the bar code reader 66 and its position where sampler 80 aspirates a portion thereof, an appropriate reagent is added at either point "SRD" or "LDD" to the reaction compartment that is timed by the executive controller 300 to receive the sample. The executive controller 300, in cooperation with slave controller 302, causes the proper reagent to be dispensed from one of the thirty-two different tabletted reagent dispensers 40 that can be accommodated by dispenser carousel 42, or, in cooperation with slave controller 306, causes the multiple liquid reagents that can be accommodated by diluent/liquid reagent dispenser 50, in response to the patient sample identification by bar code reader 66.

10

15

20

25

. 30

-18-

If a tabletted reagent is dispensed, sufficient diluent for tablet dissolution is added thereto at point "LDD" and an ultrasonic horn 14 is utilized to provide 45 seconds of high energy ultrasound to completely break up and dissolve the reagent tablet. In the preferred embodiment, this reagent mixture has a volume of about 200 microliters.

After this reconstitution of the reagent in the predetermined amount of diluent, the reaction compartment is passed to a reagent quality control analysis station at point "SAl". Here, each reagent mixture may be photometrically analyzed to verify proper reagent dispensing and dissolution. Furthermore, the executive controller 300 can also utilize this reading to adjust for any minor variation in reagent amount and resulting concentration that may exist from tablet to tablet.

Next, the reaction compartment 24 is transported to point "SD" where sample 80 will dispense the appropriate patient sample into the reaction compartment 24. As noted above, the main transport belt 32 of cuvette track 30 is carefully synchronized with the reagent dispensers and the sample to insure that the proper reaction mixture is obtained as ordered by the executive controller 300. Since sampler 80 is the only non-discrete element of the analysis system, its probe is flushed with additional diluent to prevent contamination and carry-over between samples. preferred embodiment, the final reaction volume is about 300 microliters. Following addition of the sample, the contents of the cuvettes are thoroughly mixed at air-jet mixing station 15.

10

25

30

It has been found desirable to dispense an amount of each patient sample into a reaction compartment without a reagent being added to obtain a sample blank. This sample blank value may be obtained at any or all of the last seven analysis stations as required.

The second reagent dispenser 54 is located further down the cuvette track 30 for multiple or triggered reaction capability. For example, such a reagent dispenser would be useful in conducting CKMB constituent analyses. The further air-jet mixing station 15a provides thorough mixing of the cuvette contents following this addition.

At the end of the cuvette track 30, the cuvette sealer 16 is located to seal the tops of the cuvette reaction compartments after testing for convenient and sanitary disposal of the samples. After passing through the cuvette sealer 16, the cuvette belt 22 is stripped off of the main transport belt 32 by an unloading belt 36 which removes the tested cuvettes from the water bath 12 and automatically discards them into disposal bin 18.

The solid reagent or tablet dispenser 40 utilized herein is described in detail in the aforementioned U.S. Patent 4,405,060. The reagent tablets are held in a tablet dispenser having an upper portion adapted for storing a relatively large number of tablets and a lower base with a dispensing orifice in its bottom. The dispenser carousel 42 in cooperation with executive controller 300 and slave controller 40 rotates the correct tablet dispenser to the dispensing point over the cuvette and dispenses a

tablet into the cuvette.

Assuming the correct dispenser is aligned with the cuvette, the sensing and control system unique to the present invention will now be described in detail with reference to Figures 3 to 6. As mentioned above, the dispensers 40 are driven by a motor M for dispensing the tablets one at a time, the motor being automatically engaged with the dispenser 40 that is aligned with the dispensing point "SRD". The motor M 10 is activated by a signal from the slave microprocessor 302 so as to cycle the dispenser to dispense a single tablet into the cuvette aligned therewith.

In accordance with the invention, the detector 202 is arranged at the sensing point "SRD" so 15 that it will sense whether a tablet T has actually entered the cuvette. To this end, the sensor is arranged below the level of the mouth of the cuvette and includes light sources 201 at one side of the cuvette, which project light through the optically 20 clear side faces 124 of the cuvette, and a detector 202 arranged at the opposite side of the cuvette.

In the embodiment illustrated, due to the elongated dimension of the cuvettes along the length of the belt, two side-by-side light sources are provided to give an adequate spread of light across the entire field of view through the cuvette. A single detector 202 will normally be sufficient to detect a change in light level caused by the passage of a tablet. two light emitting diodes (LEDs) 201 may be used in conjuction with a single phototransistor detector 202. It will be remembered that the cuvettes are partially immersed in water bath 12 to control the analysis

10

15

20

25

30

temperature during processing so that they are surrounded by liquid up to a predetermined level L (Figure 3). In order to provide optimum optical conditions for the detector 202, it is arranged above the water level L.

The detector 202 is connected to the slave microprocessor 302 control unit through a feedback circuit, as shown in Figures 5 and 6, which includes a signal generator 203 which generates a signal indicative of the condition sensed by the detector 202; i.e., whether or not a tablet has interrupted the light beam and thus entered the cuvette. This signal is transmitted from slave controller 302 to executive controller 300. As explained below, the executive microprocessor 300 controls subsequent operation of the analyzer in dependence upon the condition ("dispense completed" or "dispense failed") sensed by the sensor.

Thus, on receipt of a "dispense failed" signal indicating that a tablet has failed to enter the cuvette, the executive controller 300 will vary the normal or preset operation of the analyzer which has been described above. It will be understood from the foregoing that tablets will be dispensed only into selected cuvettes and in order to avoid the production of spurious "dispense failed" signals when no tablet might have been dispensed.

The sensor 200 is operatively linked to the motor M so as to be activated only when the motor M is activated to dispense a tablet. The sensor may be adapted to operate only while the motor is switched on or for a fixed time after the motor is switched on. It will be understood that while the signal generator

10

15

20

desirably produces a positive "dispense failed" signal, it may only produce a signal indicating when a tablet is successfully dispensed ("dispense completed"), the slave microprocessor 302 being programmed to recognize that the lack of a signal within a predetermined time after activation of the motor M indicates "dispense failed".

On receipt of a "dispense failed" warning, the executive controller 300 may respond in various For example, it may delay advance of the cuvette belt and activation of the other processing stations for a further "dwell" period while reactivating the tablet dispenser with the same cuvette aligned with it. Or, it may inhibit further processing of the respective cuvette in which case it will preferably process a subsequent cuvette in place thereof. detector 202 indicates repeated failure of the tablet dispenser 40; for example, where it detects two successive failures, the executive controller 300 may shut down the system for correction of the fault. audio and/or visual warning signal may be generated to indicate to an operator the non-dispensing of a tablet and/or the shut-down of the system.

By way of example, one processing cycle of
the analyzer will now be described to illustrate how
its operation may be varied upon failure of the tablet
dispenser. It will be assumed for the sake of brevity
that the processing cycle involves only three cuvettes
although it will be understood that such a cycle will
normally involve a greater number of cuvettes.

It is assumed also that the executive controller 300 has been programmed to process the

10

15

20

25

30

cuvettes as follows. The first cuvette is to receive a reagent tablet from the tablet dispenser 40, diluent from liquid dispenser 50, mixing by horn 14, a liquid biological sample from dispenser 80 and mixing by airjet mixer 15, the reaction product being read at photometric read stations SA1, SA2, SA4 and SA6. The second cuvette is to receive liquid reagent from dispenser 50, the same biological sample from dispenser 80, mixing by airjet mixer 15, further reagent from dispenser 54 and further mixing by airjet mixture 15a, the reaction products being read at photometric read stations SA1, SA2 and SA5. The third cuvette is to be processed identically to the first cuvette but receiving a different biological sample.

The cuvette belt 22 is advanced under control of the executive controller 300 to the tablet dispensing point "SRD". The solid reagent carousel has been rotated by slave controller 302 under the general direction of executive controller 300 to place the correct reagent cartridge over the cuvette. The slave controller 302 activates the motor M which in turn activates the sensor 200. Assuming that the dispenser works successfully and the tablet is dispensed into the first cuvette (cuvette "1"), the sensor beam will be interrupted and a "dispense completed" signal transmitted to the slave controller 302 by the signal generator 203. The executive controller 300 will now proceed in accordance with its preset program to advance the cuvette belt one step so that the second cuvette will be aligned with the tablet dispenser 40 at point SRD. Cuvette "l" will be between stations during this time. Cuvette "2" is not intended to receive a

10

15

20

25

30

tablet and the motor M and thus the sensor 200 will not be activated. Thus, after the normal dwell period, the belt will be advanced one further step which will bring cuvette "l" up to the diluent dispensing point "LDD" and cuvette "3" to the tablet dispensing point "SRD". The executive controller 300 now activates the diluent dispenser 50 through slave controller 306 to dispense a measured amount of diluent into cuvette "l" and at the same time the executive controller 300 activates via slave controller 302 the motor M of tablet dispenser 40 which in turn activates the sensor 200.

For the sake of description, it is assumed that at this time the dispenser 40 jams and no tablet is dispensed in cuvette "3". Since, after a predetermined timed interval the light beam from the LEDs 201 will not have been interrupted, the signal generator will generate a "dispense failed" signal and transmit this to the slave controller 302 which passes the information on the failure back to executive controller 300. Executive controller 300 will flag the results held by it for cuvette "3" so that such results will be ignored as a valid test, and will record the fact of a dispense error.

In addition, the operator is informed, such as through a printout of printer 322, that a tablet drop error has occurred at the particular dispenser in the carousel. If the operator does nothing, the analyzer will continue to operate as usual. However, there is a "pause" button on the control panel 360 through which the operator can tell the executive controller 300 to interrupt the loading of new tests in the processing stream but continue with the processing

10

15

20

25

of all those cuvette tests that had been begun. executive controller 300 interrupts the loading of new tests, cuts the cuvette belt at a point upstream of the last cuvette selected for a test and places the solid reagent slave controller 302 into a manual mode so that the operator can manually replace the faulty cartridge. Then the operator pushes the start button on control panel 360 which informs the executive controller 300 to restart the feeding of the cuvettes to the solid reagent station "SRD", start loading new tests from the point it left off, and remove the solid reagent slave controller 302 from its manual mode. The "pause" mode selection, of course, can be done automatically in response to the detection of the "dispense failed" signal.

Instead of interrupting the advance of the cuvettes and repeating the dispensing step on the same cuvette, as described above, the microprocessor system may be programmed to repeat the tablet dispensing step on the next cuvette ("4") in line and treat this cuvette as the third cuvette during the remainder of the processing steps. According to this sequence, upon successive dispensing failures, the machine will shut down as described above the cuvette "4" will remain aligned with dispensing point "SRD" when the machine is restarted. It will be understood that this sequence may be less practical where tablet dispensing is not the first processing step.

Figure 5 shows a schematic illustration of one embodiment of the control system for the analyzer. Any suitable control system, or elements thereof, can be used. For instance, the executive or main

10

15

20

25

30

controller 300 may be a DEC "MICRO 11" computer system sold by DIGITAL Equipment Corporation, Maynard, Massachusetts. It is tied by a suitable computer link to data management controller console 340. The executive controller 300 controls the overall system by communicating with various analyzer stations and the console 340 which runs calculations, programs, etc. In addition, executive controller 300 keeps track of test conditions, the overall timing and the system's state (run, stop, etc), and stores the readings from the analyzer tests. A systems status monitor 330 which reads voltages, performs diagnostics, checks various system status, etc., communicates to the executive controller 300 through its slave controller 328.

The slave controllers 302, 306, 310, 314, 316 and 324 can be 8741 microprocessors sold by Intel Corporation, Santa Clara, California. Slave controllers 322 and 328 can be 8742 and 8748 microprocessors, respectively, also sold by Intel Corporation. All of these processors are in the 8048 Intel family. The executive controller 300 can be a 280, Zilog Processor sold by Exxon Corporation, NY, NY.

Key board 362, shears 28, mixing stations 14, 15, 15a, cuvette drive and cuvette sealer 16, control panel 360 and alarm 364 are connected directly through a suitable I/O (Input/Output) interface to controller 300. The stations for tablet dispensing 40, liquid reagent dispensing 50, 54, photoread of the cuvette contents 90, printer 322, transfer carousel and bar code reader 64, 66 and systems status monitor 330 are tied into the executive computer 300 through their associated slave controllers 302, 306, 310, 320, 324,

10

15

20

25

328, respectively. Sample dispenser 80 uses two slave controllers 314, 316 to link it to the executive controller 300.

Although particular configurations and features of the present invention have been discussed in connection with the above-described preferred embodiments thereof, it should be understood that those skilled in the art may make various changes, modifications and substitutions thereto without departing from the spirit and scope of the invention as defined in the appended claims.

For example, although the system described above has only one tablet dispensing point "SRD", it is within the scope of this invention that two or more tablet dispensing locations be provided, each one having its own sensor and feedback to the slave and executive controllers.

In the embodiment of analyzer described herein, a tablet from dispenser 40 is loaded into an empty cuvette. However, the cuvette may have been previously charged with a liquid; e.g., diluent, so that the cuvette contains liquid to a predetermined level therein. This liquid may be present whether or not there is liquid surrounding the cuvette and may extend to a different level. For the same reason of optical clarity explained above in relation to the water bath 12, in such a case the sensor 200 is desirably arranged above the liquid level in the cuvette.

The patents and patent applications referred to herein are all hereby incorporated by reference herein in their entirities.

-28-

Although the present invention as described above is embodied in a clinical analyzer for biological samples, it will be understood that it is equally suited to other applications which involve the selective dispensing of tablets into containers. Thus, it may for example be employed in any chemical analyzer where tablets are dispensed into selected containers advanced past the tablet dispenser.

#### CLAIMS

 A clinical analysis system for analyzing biological samples, including:

a plurality of processing stations,

means for successively advancing cuvettes past said processing stations in turn, and

control means for selectively activating said processing stations with respect to said cuvettes, whereby different cuvettes are differently processed,

one of said processing stations comprising a tablet dispensing means and sensing means arranged to sense whether a tablet has entered a cuvette aligned with said dispensing means, said sensing means being activated only when said tablet dispensing means is activated, and

said control means being responsive to said sensing means in dependence upon the condition sensed by said sensing means.

2. A clinical analysis system according to Claim l including means for defining a liquid level at a predetermined height in a cuvette aligned with the tablet dispensing means, said sensing means being arranged at a level below the mouth of a cuvette so

aligned and above said liquid level.

- 3. A clinical analysis system according to Claim l in which said sensing means includes two light sources.
- 4. A clinical analysis system according to Claim l in which said tablet dispensing means includes a motor for driving the dispensing means to dispense a tablet and said sensing means is only active when said motor is in operation.
- 5. A clinical analysis system according to Claim l in which said tablet dispensing means includes a motor for driving the dispensing means to dispense a tablet and said sensing means is activated for a timed interval each time said motor is activated.
- 6. A clinical analysis system according to Claim l including signal generating means associated with said sensing means for generating a signal indicating the absence of a tablet, said control means being repsonsive to said signal to vary the subsequent operation of said system.
- 7. A clinical analysis system according to Claim 6 in which said control means varies said operation by inhibiting advance of the cuvettes and reactivating the tablet dispensing means.
- 8. A clinical analysis system according to Claim 6 in which said control means varies said operation by

inhibiting further processing of said cuvette aligned with the tablet dispensing means and processing a subsequent cuvette in its place.

- 9. A clinical analysis system according to Claim l including audio and/or visual warning means for indicating the absence of a tablet to an operator.
- 10. In a method of analyzing biological samples in which successive cuvettes are advanced past a plurality of processing stations in turn and said processing stations are selectively activated with respect to said cuvettes whereby different cuvettes are differently processed, one of said processing stations comprising a tablet dispensing means, the improvement comprising sensing whether a tablet has entered a respective cuvette aligned with the tablet dispensing means only each time the tablet dispensing means is activated and controlling subsequent activation of said processing stations in dependence whether the entry of a tablet into a cuvette has been sensed.
- 11. Apparatus for dispensing tablets into selected containers advanced therepast, including:

a tablet dispenser,

control means for activating said tablet dispenser to dispense a tablet into a container, and

sensing means arranged to sense whether a tablet has entered the container, said sensing means being activated only when said tablet dispenser is activated and said control means being responsive to said sensing means in dependence upon the condition sensed by said sensing means.


- 12. Apparatus for dispensing tablets according to Claim 11 in which said sensing means includes two light sources.
- 13. Apparatus for dispensing tablets according to Claim 11 in which said tablet dispenser includes a motor for driving the tablet dispenser to dispense a tablet and said sensing means is active only when the motor is in operation.
- 14. Apparatus for dispensing tablets according to Claim 11 in which said tablet dispenser includes a motor for driving the tablet dispenser to dispense a tablet and said sensing means is activated for a timed interval each time said motor is activated.
- 15. Apparatus for dispensing tablets according to claim 11, further including means for aligning said solid tablet dispenser with solid container.
- 16. A method for dispensing tablets in which tablets are dispensed into selected cuvettes advanced in turn past a tablet dispensing means, including the steps of:

advancing containers in turn past the tablet dispensing means,

selectively activating said tablet dispensing means,

sensing whether a tablet has entered a container only each time the tablet dispensing means is activated, and

controlling subsequent step (a) and/or step (b) on dependence whether the entry of a tablet into a container has been sensed.



2/4






FIG. 2.

3/4







			International Application No PCT	/US85/01851	
I. CLASSIFICA	TION OF SI	JBJECT MATTER (if several classifi	cation symbols apply, indicate all) *		
According to Inte	rnational Pate	ent Classification (IPC) or to both Nation	onal Classification and IPC		
INT. CL4	GOIN 2	21/00,31/00,33/00,	35/02; B01L 3/00; (	C12M 1/34;1/36	
U.S. CL.	444/03	<u>5,64,65,67,99,100,</u>	102; (See Attachme	ent)	
II. FIELDS SEA	RCHED				
		Minimum Documen	tation Searched 4		
Classification Syst	em		Classification Symbols		
	1122	63,64,65,67,99,10	0 102		
U.S.			0,102		
0.5.		289,291,808	•		
	1441/	2,3,5,7; 250/576		<del></del>	
		Documentation Searched other to to the Extent that such Documents	nan Minimum Documentation are included in the Fields Searched 6		
III DOGUMENT	re courie	EDER TA DE DELEVALE.			
		ered to be relevant 14 cument, 16 with indication, where appr	ropriate, of the relevant passages 17	Relevant to Claim No. 18	
		· · · · · · · · · · · · · · · · · · ·		1	
Y	N, Pr	oduct Brochure: "T	This is Paramax,	1-16	
1		e Paramax Analytic			
	Am				
-		spital Supply Corp			
-	Fl	orida, Distributed	d by American		
	Sc				
1		]			
ł		Graw Park, Illinoi	apply Corporation,		
		ne 20, 1983, 12 pa			
	5 4	ne 20, 1503, 12 pe	iges.		
Y, P	IIS.A.	4,528,159 publish	ned 09 July 1985.	1-16	
-/-	00/11/	Liston.	ded of oury 1903,	1 10	
		HISCOII.			
x	TP.A.	56-76050 publishe	ad 23 June 1981.	11,15,16	
	01 /11/	30 70030 Publishe	sa 25 dane 1701.	11,13,10	
1					
Y	n	17		1-10,12-	
-				14	
1					
1					
• Special cates	ories of cited	documents: 19	"In later document published after t	he international filling date	
* Special categories of cited documents: 15  "A" document defining the general state of the art which is not cited to understand the principle or theory underlying				ct with the application but	
considered	d to be of par	ticular relevance	invention	e or theory underlying the	
"E" earlier doc filing date		blished on or after the international	"X" document of particular relevan cannot be considered novel or	ce; the claimed invention	
"L" document	which may th	nrow doubts on priority claim(s) or	involve an inventive step		
which is cited to establish the publication date of another citation or other special reason (as specified)			"Y" document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the		
"O" document other mea	referring to a	n oral disclosure, use, exhibition or	document is combined with one	or more other such docu-	
		or to the international filing date but	ments, such combination being in the art.	opylona to a betaou amilied	
later than	the priority da	ite claimed	"&" document member of the same	patent family	
IV. CERTIFICA					
Date of the Actu	ai Completion	of the International Search *	Date of Mailing of this International So	. <u>-</u>	
10 n	ecembe	r 1985 ·	17DEC	1985	
International Sea			Signature of Authorized Officer 20		
		,	1165 01		
ISA/	US		Randall E. Deck		
			THE LICE LICE		

PCT/US85/01851

# ATTACHMENT

I. CLASSIFICATION OF SUBJECT MATTER:

U.S. CL. 435/289,291,808; 221/2,3,5,7; 250/576

	International Application No. PCT/US85/01851			
FURTHE	R INFORMATION CONTINUED FROM THE SECOND SHEET			
Y.	US,A, 4,130,394 published 19 December 1978, Negersmith (see column 4, line:67-column 5, line 4).	9		
Y	US,A, 4,101,383 published 18 July 1978, Wyatt et al. (see column 13, line 67-column 14, line 4).	15		
Y	US,A, 3,665,980 published 30 May 1972, Croslin et al. (see column 2, lines 20-23).	15		
V. □ OB	SERVATIONS WHERE CERTAIN CLAIMS WERE FOUND UNSEARCHABLE 10	·		
	This international search report has not been established in respect of certain claims under Article 17(2) (a) for the following reasons:			
1. Clai	m numbers, because they relate to subject matter 12 not required to be searched by this Aut	hority, namely:		
	•			
	m numbers, because they relate to parts of the international application that do not comply w	ith the prescribed require-		
men	ts to such an extent that no meaningful international sparch can be carried out 13, specifically:			
	•			
VI. OE	SERVATIONS WHERE UNITY OF INVENTION IS LACKING 11			
	SERVATIONS WHERE UNITY OF INVENTION IS EXCEINED.	<del></del>		
This Inter	national Searching Authority found multiple inventions in this international application as follows:			
1. As a	Ill required additional entrals force were timely asid by the angle of the later when the			
of th	ill required additional search fees were timely paid by the applicant, this international search report co e international application.	vers all searchable claims		
	only some of the required additional search fees were timely paid by the applicant, this international	search report covers only		
thos	e claims of the international application for which fees were paid, specifically claims:			
	• .			
	equired additional search fees were timely paid by the applicant. Consequently, this international sean envention first mentioned in the claims; it is covered by claim numbers:	rch report is restricted to		
4. As.	ill searchable claims could be searched without effort justifying an additional fee, the international Se	earching Authority did not		
	e payment of any additional fee.			
Remark or				
☐ The	additional search fees were accompanied by applicant's protest.			

International Application No.

II. DOCUM	ENTS CONSID	ERED TO BE RELEVANT (CONTINUED FROM THE SECOND	SHEET)
ategory * ;	Citation of D	ocument, $^{16}$ with indication, where appropriate, of the relevant passages $^{1}$	Relevant to Claim No
<b>A</b>	US, A,	4,276,383 published 30 June 1981, Leighton et al.	1-16
A	US, A,	4,405,060 published 20 September 1983, Hsei.	1-16
A	US,A,	4,420,566 published 13 December 1983, Jessop et al. (see column 2, lines 38-44).	1-16
A	JP,A,	58-95262 published 06 June 1983.	1-16
			1
		•	
			: : !
			i i
:			
:			; . · · · · · · · · · · · · · · · · · ·
			•
:			
:			;
		•	:

# This Page is Inserted by IFW Indexing and Scanning Operations and is not part of the Official Record

# **BEST AVAILABLE IMAGES**

Defective images within this document are accurate representations of the original documents submitted by the applicant.

Defects in the images include but are not limited to the items checked:

□ BLACK BORDERS
□ IMAGE CUT OFF AT TOP, BOTTOM OR SIDES
□ FADED TEXT OR DRAWING
□ BLURRED OR ILLEGIBLE TEXT OR DRAWING
□ SKEWED/SLANTED IMAGES
□ COLOR OR BLACK AND WHITE PHOTOGRAPHS
□ GRAY SCALE DOCUMENTS
□ LINES OR MARKS ON ORIGINAL DOCUMENT
□ REFERENCE(S) OR EXHIBIT(S) SUBMITTED ARE POOR QUALITY

# IMAGES ARE BEST AVAILABLE COPY.

OTHER:

As rescanning these documents will not correct the image problems checked, please do not report these problems to the IFW Image Problem Mailbox.